

DACW66-01-B-0011 Harmon Sewer Culvert, Levee District No. 3, MS County, MO			
Quantities Last Updated:			5/21/01 7:15 AM
Item	Quantity Calculations Description For Lump Sum Items	Estimated Quantity	U/M
1	Mobilization & Demobilization	1	LS
2	Environmental Protection	1	LS
2.a	Erosion Control	1,700	LF
3	Clearing and Grubbing	1	LS
3.a	Clearing and Grubbing	6.81	AC
4	Dewatering	1	LS
4.a	Estimated Wells	3	EA
10	Wall Drain	1	LS
10.a	4" Perforated Pipe	34	LF
10.b	4" Solid Pipe	32	LF
10.c	45 Degree Elbows	4	EA
10.d	4" Flapgate & Outlet Screen	2	EA
10.e	Geotextile Fabric	92	SY
10.f	Gravel	21	TN
10.g	Concrete at Cleanouts	0.36	CY
19	Turf	1	LS
19.a	Turfing	4.60	AC
20	Temporary Earthen Cofferdam Construction	1	LS
20.a	Cofferdam at Inlet	200	CY
20.b	Cofferdam at Outlet	56	CY
21	Outfall Structure	1	LS
21.a	Concrete	159	CY
21.b	Reinforcing	9	TN
22	Grouting	1	LS
22.a	Contractor Design	1	LS
23	Bridge Foundations	1	LS
23.a	Concrete	5	CY
23.b	Reinforcing	181	LB
24	Structural Steel and Miscellaneous	1	LS
24.a	Walkway Bridge Structural Steel	7,000	LB
24.b	Grating	2,127	LB
24.c	Handrail and Ladder Rungs	2,654	LB
24.d	8' Security Fence and Gate	10.17	LF
25	Sluice Gate and Gate Lift Assembly	1	LS
25.a	5.5' X 5.5' Sluice Gate and Operator	2	EA
25.b	Portable Gas Driven Actuator	1	EA

It is to be expressly understood that the accuracy of these estimates is in no way warranted and that the furnishing of this information to a bidder will not relieve him of his responsibility to estimate the quantities involved. It is further to be expressly understood that in no case will such estimate be used as a basis of claim against the Government.