MATCHLINE STA. 25+00 SHEET C1.02

MATCHLINE STA. 40+00 SHEET C1.04

MH 3–STA 25+00±
Δ=6°6'14"LT

MH 4–STA 31+00±
Δ=0°00'00"

BARRY BRIDGEFORTH ETAL

CAMP CREEK CANAL

CE

E

30' TEMPORARY CONSTRUCTION EASEMENT

50' PERMANENT EASEMENT

600± LF OF 48" SANITARY SEWER

900± LF OF 48" SANITARY SEWER

TBM

272'

26+00 27+00 28+00 29+00 30+00 31+00 32+00 33+00 34+00 35+00 36+00 37+00 38+00 39+00 40+00

TBM STA. 32+50±
RAILROAD SPIKE IN 8" BIRCH
ELEV.: 272.89'
N: 1952825.7651
E: 2432809.1601

PLAN
1"=100'

50 0 50 100 150

CONTRACTOR NOTE: ALL EXISTING UTILITIES ON THESE PLANS ARE FOR INFORMATION ONLY. NO GUARANTEE IS OFFERED OR TO BE IMPLIED REGARDING THE ACCURACY OF THE LOCATIONS OF EXISTING UTILITIES INDICATED ON THESE PLANS. THE CONTRACTOR IS RESPONSIBLE FOR ACCURATELY DETERMINING THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION.

NEW 108" DIA. MH
STA. 25+00
RIM ELEVATION
@ 274.8±

NEW 96" DIA. MH
STA. 31+00
RIM ELEVATION
@ 276.2±

MATCHLINE STA. 25+00

MATCHLINE STA. 40+00

100-Year

APPROXIMATE
100 YEAR FLOOD

APPROXIMATE
EXISTING GRADE

INV IN 248.40

INV OUT 248.94

INV IN 249.04

600± LF OF 48" SANITARY SEWER AT 0.00090 FT/FT SLOPE

900± LF OF 48" SANITARY SEWER AT 0.00090FT/FT SLOPE

300 290 280 270 260 250 240 230 220 210

25+00 +50 26+00 +50 27+00 +50 28+00 +50 29+00 +50 30+00 +50 31+00 +50 32+00 +50 33+00 +50 34+00 +50 35+00 +50 36+00 +50 37+00 +50 38+00 +50 39+00 +50 40+00

PROFILE
HORZ: 1"=50'
VERT: 1"=10'

NO.	DATE	NATURE	BY	APP'D
		REVISIONS		

DESIGNED TMH	DATE OCTOBER 2003
DRAWN TMH	SCALE AS NOTED
CHECKED CRF	JOB NO. 16535.05

EAIWEI, LLC
WAGGONER
660 BRIARWOOD DRIVE SUITE 515
JACKSON, MS 39206

100% SET

DESOTO COUNTY REGIONAL UTILITY AUTHORITY
UPPER CAMP CREEK INTERCEPTOR SOUTH
DESOTO COUNTY, MISSISSIPPI

DESOTO COUNTY REGIONAL UTILITY AUTHORITY

PLAN AND PROFILE SHEET
STA. 25+00 to STA. 40+00

PROJECT NO.	
16535.05	
CONTRACT	SHEET
1	C1.03