MATCHLINE STA. 100+00 SHEET C1.07

MATCHLINE STA. 115+00 SHEET C1.09

MH 12–STA 100+00±
Δ=0°00'00"RT

MH 13–STA 109+00±
Δ=0°00'05"

STEPHAN D. WILLIAMS

ROBERT F. WILLIAMS

EXISTING 30" RISER PIPE AND CMP DRAIN

280'

290'

30' TEMPORARY CONSTRUCTION EASEMENT

50' PERMANENT EASEMENT

30' TEMPORARY CONSTRUCTION EASEMENT

900± LF OF 48" SANITARY SEWER

B-7

TBM

CAMP CREEK CANAL

TBM STA. 111+00±
TOP OF #5 REBAR
ELEV.: 281.81'
N: 1960818.0234'
E: 2433702.1508'

PLAN
1"=100'

CONTRACTOR NOTE: ALL EXISTING UTILITIES ON THESE PLANS ARE FOR INFORMATION ONLY. NO GUARANTEE IS OFFERED OR TO BE IMPLIED REGARDING THE ACCURACY OF THE LOCATIONS OF EXISTING UTILITIES INDICATED ON THESE PLANS. THE CONTRACTOR IS RESPONSIBLE FOR ACCURATELY DETERMINING THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION.

NEW 96" DIA. MH STA. 100+00 RIM ELEVATION @ 284.00'±

EXISTING CMP DRAIN STA. 107+49

NEW 96" DIA. MH STA. 109+00 RIM ELEVATION @ 285.2'±

NEW 96" DIA. MH STA. 115+00 RIM ELEVATION @ 286.4'±

APPROXIMATE 100 YEAR FLOOD

APPROXIMATE EXISTING GROUND

100–Year

MATCHLINE STA. 100+00

MATCHLINE STA. 115+00

INV IN 255.90

INV OUT 256.70

INV IN 256.80

INV OUT 257.33

900± LF OF 48" SANITARY SEWER AT 0.00090 FT/FT SLOPE

600± LF OF 48" SANITARY SEWER AT 0.00090 FT/FT SLOPE

PROFILE
HORZ: 1"=50'
VERT: 1"=10'

NO.	DATE	NATURE	BY	APP'D
		REVISIONS		

DESIGNED TMH	DATE OCTOBER 2003
DRAWN TMH	SCALE AS NOTED
CHECKED CRF	JOB NO. 16535.05

EAIWEI, LLC
WAGGONER
460 BRIARWOOD DRIVE SUITE 515
JACKSON, MS 39206

100% SET

DESOTO COUNTY REGIONAL UTILITY AUTHORITY
UPPER CAMP CREEK INTERCEPTOR SOUTH
DESOTO COUNTY, MISSISSIPPI

DESOTO COUNTY REGIONAL UTILITY AUTHORITY

PLAN AND PROFILE SHEET
STA. 100+00 to STA. 115+00

PROJECT NO.	
16535.05	
CONTRACT	SHEET
1	C1.08