MATCHLINE STA. 205+00 SHEET C1.14

MATCHLINE STA. 220+00 SHEET C1.16

EXISITNG 30" RISER PIPE CMP DRAIN IN VICNITY

MH 26–STA 210+00±
Δ=0°00'00"

MH 27–STA 217+00±
Δ=1°42'55"RT

30' TEMPORARY CONSTRUCTION EASEMENT

50' PERMANENT EASEMENT

30' TEMPORARY CONSTRUCTION EASEMENT

500± LF OF 48" SANITARY SEWER

700± LF OF 48" SANITARY SEWER

300± LF OF 48" SANITARY SEWER

B-14

B-15

TBM

CAMP CREEK CANAL

TBM STA. 211+50±
TOP OF 1/2" REBAR
ELEV.: 295±18'
N: 1970543.4092
E: 2434997.3469

PLAN
1"=100'

CONTRACTOR NOTE: ALL EXISTING UTILITIES ON THESE PLANS ARE FOR INFORMATION ONLY. NO GUARANTEE IS OFFERED OR TO BE IMPLIED REGARDING THE ACCURACY OF THE LOCATIONS OF EXISTING UTILITIES INDICATED ON THESE PLANS. THE CONTRACTOR IS RESPONSIBLE FOR ACCURATELY DETERMINING THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION.

NEW 96" DIA MH
STA. 210+00
RIM ELEVATION
@ 298.1±

NEW 96" DIA MH
STA. 217+00
RIM ELEVATION
@ 299.3'±

APPROXIMATE 100 YEAR FLOOD

100–Year

APPROXIMATE EXISTING GROUND

500± LF OF 48" SANITARY SEWER AT 0.00072 FT/FT SLOPE

700± LF OF 48" SANITARY SEWER AT 0.00072 FT/FT SLOPE

300± LF OF 48" SANITARY SEWER AT 0.00072 FT/FT SLOPE

INV OUT 265.79
INV IN 265.89

INV OUT 266.39
INV IN 266.49

PROFILE
HORZ: 1"=50'
VERT: 1"=10'

NO.	DATE	NATURE	BY	APP'D
		REVISIONS		

DESIGNED TMH	DATE OCTOBER 2003
DRAWN TMH	SCALE AS NOTED
CHECKED CRF	JOB NO. 16535.05

EAI/WEI, LLC
WAGGONER
660 BRIARWOOD DRIVE SUITE 515
JACKSON, MS 39206

100% SET

DESOTO COUNTY REGIONAL UTILITY AUTHORITY
UPPER CAMP CREEK INTERCEPTOR SOUTH
DESOTO COUNTY, MISSISSIPPI

DESOTO COUNTY REGIONAL UTILITY AUTHORITY

PLAN AND PROFILE SHEET
STA. 205+00 to STA. 220+00

PROJECT NO.	
16535.05	
CONTRACT	SHEET
1	C1.15