

W912EQ-04-B-0011 Gravity Flow Culvert Replacement No. 3, New Madrid, MO			
Quantities Last Updated: (Amendments-none)		6/29/04 7:12 AM	
Item	Quantity Calculations Description For Lump Sum Items	Estimated Quantity	U/M
1	Mobilization & Demobilization	1	LS
2	Environmental Protection	1	LS
3	Control of Water	1	LS
4	Demolition	1	LS
5	Clearing & Grubbing	1	LS
5a	Clearing	3.3	AC
6	Excavation	1	LS
6a	Excavation	500	CY
7	Pervious Backfill	1	LS
7a	Pervious Backfill	72	CY
8	Wall Drain	1	LS
9	Riprap "R 90"	667	TN
10	Turfing	1	LS
10a	Turfing	3.3	AC
11	Reinforced Concrete Culvert Pipe, 36-inch diameter	1	LS
11a	Reinforced Concrete Culvert Pipe, 36-inch diameter	172	LF
12	Geotextile (Filter Fabric)	1	LS
12a	Geotextile (Filter Fabric)	782	SY
13	Cast-in-Place Concrete	1	LS
13a	Cast-in-Place Concrete	68	CY
14	Sluice Gate & Gate Lift Assembly	1	LS
15	Pressure Grouting	1	LS
15a	Pressure Grouting	630	CF
16	Structural Steel and Miscellaneous Metals	1	LS
16a	Structural Steel and Miscellaneous Metals	8,800	LB

It is to be expressly understood that the accuracy of these estimates is in no way warranted and that the furnishing of this information to a bidder will not relieve him of his responsibility to estimate the quantities involved. It is further to be expressly understood that in no case will such estimate be used as a basis of claim against the Government.