

Project: ITEM NO. R-48.88 A.C. (PARCEL NO.2) RELIEF WELLS
 Location: Cape Girardeau and Scott Counties (Nash), MO
 W912EQ-05-B-0001

BI #	BID ITEM	Qty	UM
1	Mobilization & Demobilization	1	LS
2	Clearing	1	LS
	may vary	34	AC
3	Excavation	37,500	CY
4	Relief Wells 8"	1,775	LF
	Drilling (sub)	22	EA
	Gravel (25% waste)	260	TN
	Screen pipe	1,430	LF
	Riser pipe (1' extra/ea well)	367	LF
	Concrete	14	CY
	Grout Mix (in place)	23	CY
	Bentonite (in grout mix)	1,030	LBS
	Sand	4	TN
	Well guard	22	EA
	Check valve	22	EA
	Angular face ring	22	EA
	Bottom plate	22	EA
	Chemical, HTH	51	LB
5	Relief Wells 10"	4,546	LF
	Drilling (sub)	53	EA
	Gravel (25% waste)	620	TN
	Screen pipe	3,445	LF
	Riser pipe (1' extra/ea well)	1,154	LF
	Concrete	33	CY
	Grout Mix (in place)	51	CY
	Bentonite (in grout mix)	2,500	LBS
	Sand	9	TN
	Well guard	53	EA
	Check valve	53	EA
	Angular face ring	53	EA
	Bottom plate	53	EA
	Chemical, HTH	204	LB
6A	First 150 Hours	150	HR
6B	All Over 150 Hours	45	HR
7	Pilot Hole Boring	7,446	LF
	Seive analysis test	1,950	EA
8	Piezometers	407	LF
9	Guard Posts	261	EA
10	Riprap "R-90"	10,100	TN
11	Geotextile	16,188	SY
12	Aggregate Surfacing	1	LS
	Compacted cubic yards	140	CY
13	Corrugated Metal Pipe, 24-Inch	114	LF
14	Corrugated Metal Pipe, 28X20	88	LF
15	Corrugated Metal Pipe, 42X29	170	LF
16	Corrugated Metal Pipe, 48-Inch	228	LF
17	Establishment of Turf	1	LS

BI #	BID ITEM	Qty	UM
	(none inside ditches)	8	AC
18	Environmental Protection	1	LS

See Section 700, paragraph 52.0-4048, entitled "QUANTITY ESTIMATES" for responsibility of contractors.

This clause was added by page 2 of amendment 1.

If you find errors in these, we would appreciate your comments.

Quantities as of 3/2/05

Quantities reflect one Amendment.

You may contact Richard Hurst for questions on these quantities.

You may email him at

Richard.H.Hurst@MVM02.USACE.ARMY.MIL

If you do not have email, you may contact him at 901.544.0886.