File: 05B0007 Qty for Web page.xls

## FRANCIS BLAND FLOODWAY DITCH; ITEM 2, PHASE 2, CHANNEL ENLARGEMENT GREENE COUNTY, AR; SFBP - CONSTRUCTION W912EQ-05-B-0007

| BI# | BID ITEM                             | Qty     | UM |
|-----|--------------------------------------|---------|----|
| 1   | Mobilization & Demobilization        | 1       | LS |
| 2   | Clearing and Cleanout                | 1       | LS |
|     | Total length:                        | 18,725  | LF |
|     | Overbank acres                       | 49      | AC |
| 3   | Excavation                           | 385,000 | CY |
| 4   | Filter Material                      | 32,500  | TN |
| 5   | Riprap R-200                         | 120,000 | TN |
| 6   | Riprap R-650                         | 3,650   | TN |
| 7   | Grout for Key Protection Gabions     | 1,600   | CY |
| 8   | Stone Filled Wire Mesh Gabions       | 14,210  | SY |
|     | Gabions                              | 510     | SY |
|     | Gabion Matress                       | 13,700  | SY |
| 9   | Culvert Cutoff with Riprap Placement | 8       | EA |
| 10  | Corrugated Metal Pipe, 24-inch       | 50      | LF |
| 11  | Corrugated Metal Pipe, 48-inch       | 50      | LF |
| 12  | Flared End Section, 24-inch          | 2       | EA |
| 13  | Flared End Section, 48-inch          | 1       | EA |
| 14  | Establishment of Turf                | 75      | AC |
| 15  | Silt Fences                          | 4,385   | LF |
| 16  | Erosion Control Blanket              | 58,500  | SY |
| 17  | Environmental Protection             | 1       | LS |

See Section 100, page 5 of 159, paragraph entitled "QUANTITY ESTIMATES" for responsibility of contractors. If you find errors in these, we would appreciate your comments. Quantities as of 3/11/05.

Quantities reflect no Amendments.

You may contact Richard Hurst for questions on these quantities.

You may email him at

'Richard.H.Hurst@MVM02.USACE.ARMY.MIL

If you do not have email, you may contact him at 901.544.0886.