

<b>AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT</b>				1. CONTRACT ID CODE J		PAGE OF PAGES 1   2	
2. AMENDMENT/MODIFICATION NO. 0001		3. EFFECTIVE DATE 08-Jul-2005	4. REQUISITION/PURCHASE REQ. NO. W38XGR-5152-7077			5. PROJECT NO.(If applicable) W912EQ-05-B-0016	
6. ISSUED BY US ARMY ENGINEER DISTRICT, MEMPHIS 167 N MAIN STREET B202 MEMPHIS TN 38103-1894		CODE W912EQ	7. ADMINISTERED BY (If other than item 6) <b>See Item 6</b>				
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)				X	9A. AMENDMENT OF SOLICITATION NO. W912EQ-05-B-0016		
				X	9B. DATED (SEE ITEM 11) 17-Jun-2005		
					10A. MOD. OF CONTRACT/ORDER NO.		
					10B. DATED (SEE ITEM 13)		
CODE		FACILITY CODE					
<b>11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS</b>							
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer <input type="checkbox"/> is extended, <input checked="" type="checkbox"/> is not extended. Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.							
12. ACCOUNTING AND APPROPRIATION DATA (If required)							
<b>13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.</b>							
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.							
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).							
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:							
D. OTHER (Specify type of modification and authority)							
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.							
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) This solicitation for County Bridge Replacement 10 & 15 Mile Bayou at Mile 18.8 scheduled to open at 2:30 p.m. on 19 Jul 2005 is amended as follows:  SPECIFICATIONS  1. Section 00010, Bid Schedule - Delete pages 3 and 4 of the Bid Schedule and replace with the attached revised pages 3 and 4 of the Bid Schedule.  2. Section 01270A, TOC, 1.3.6 - Replace "48-inch" with "36-inch".							
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.							
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)			
				TEL:		EMAIL:	
15B. CONTRACTOR/OFFEROR		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA		16C. DATE SIGNED	
_____ (Signature of person authorized to sign)				BY _____ (Signature of Contracting Officer)		08-Jul-2005	

## SECTION SF 30 BLOCK 14 CONTINUATION PAGE

**The following items are applicable to this modification:**

3. Section 01270A, Paragraph 1.3.4 (b): Delete “Riprap will be measured for payment by the ton.” and replace with the following paragraph:

“Riprap will be measured for payment by the ton (2,000 pounds) by weighing each truckload to the nearest 0.1 ton, and the final quantity of the whole sum will be rounded to the nearest whole ton. The riprap will be measured for payment by being weighed on approved scales before being placed in the work. Quarry weights will not be accepted. Scales shall be of sufficient length to permit simultaneous weighing all axle loads and shall be inspected, tested and sealed as directed to assure accuracy with 0.5 percent throughout the range of the scales. The scales, located at the site of the work, shall be certified as to accuracy by an acceptable scales company representative prior to weighing any riprap. Scales will be checked and certified before riprap hauling and rechecked and recertified whenever a variance is suspected. The Contractor shall furnish the scales. If commercial scales are readily available in close proximity 10 miles of site of work, the Contracting Officer may approve the use of the scales. The riprap shall be weighed in the presence of the Government representative. The Contracting Officer may elect to accept certified weight certificates furnished by a public weighmaster in lieu of scale weights at the jobsite.”

4. Section 01270A, Paragraph 1.3.6: Replace “48-inch” with “36-inch”

5. Section 01270A, Paragraph 1.3.6 (a): Replace “48-inch” with “36-inch”

6. Section 01357: Delete section in its entirety and replace with the attached revised Section 01357.

7. Section 02300, Paragraph 3.2: Add the following to the end of the paragraph:

“All excavation shall be performed by first removing earthen material from the top bank and then proceeding down to the toe of the slope. At no time shall the channel bottom be excavated before the channel slopes. Slides resulting from excavating the channel slopes steeper than recommended on the plans or excavating the channel bottom before the top bank shall be the responsibility of the contractor.”

8. Section 02300, Paragraph 3.2.3 Dewatering: Delete the paragraph in its entirety.

## PLANS

9. Drawing 1, MAPS AND INDEX, drawing no. 001a0710 DRAWING INDEX: Make the following pen and ink changes to the drawing:

DRWG No.: add the following, “ER-1”

DRAWING TITLE: add the following, “TEMPORARY EROSION CONTROL DEVICES”

PROJ. ID: add the following, “51”

FILE NO.: add the following, “001a0208”

10. Add Drawing “001a0208”. The new drawing can be viewed under Plans on the webpage.

Section 00010 - SOLICITATION CONTRACT FORM

COUNTY BRIDGE REPLACEMENT 10 AND 15 MILE BAYOU, ITEM 2 MILE 18.8  
 BID SCHEDULE

ITEM NO	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
0001	Mobilization & Demobilization	1	Lump Sum	XXX.XX	_____
0002	Clearing and Grubbing	1	Lump Sum	XXX.XX	_____
0003	Excavation	34,000	Cubic Yard	_____	_____
0004	Roadway and Field Access Ramp	1	Lump Sum	XXX.XX	_____
0005	Aggregate Surfacing	490	Net Ton (2,000 LB)	_____	_____
0006	Finish Dressing, Fertilizing, Seeding, and Mulching	1	Lump Sum	XXX.XX	_____
0007	Bedding Material	600	Net Ton (2,000 LB)	_____	_____
0008	Riprap	1,200	Net Ton (2,000 LB)	_____	_____

0009	Steel H-piles	2,640	Linear Foot	_____	_____
0010	Cast-in-Place Structural Concrete	1	Lump Sum	XXX.XX	_____
0011	Corrugated Metal Pipe, 36-inch	40	Linear Foot	_____	_____
0012	Guardrail	1	Lump Sum	XXX.XX	_____
0013	Environmental Protection	1	Lump Sum	XXX.XX	_____
0014	Bridge at Mile 18.80	1	Lump Sum	XXX.XX	_____
0015	Bridge Demolition	1	Lump Sum	XXX.XX	_____

GRAND TOTAL ITEMS 0001 THRU 0015 \_\_\_\_\_

NOTES

Bidders shall furnish unit prices for all items listed on the schedule of bid items that require unit prices. If the bidder fails to insert a unit price in the appropriate blank for required items, but does furnish an extended total or an estimated amount for such items, the Government will deem his unit price to be the quotient obtained by dividing the extended amount for that line item by the quantity. IF THE BIDDER OMITTS BOTH THE UNIT PRICE AND THE EXTENDED ESTIMATED AMOUNT FOR ANY ITEM, HIS BID WILL BE DECLARED NONRESPONSIVE.

SECTION 01357

STORM WATER POLLUTION PREVENTION PLAN

10 and 15 Mile Bayou, Item 2, County Bridge Replacement at mile 18.8  
STORM WATER POLLUTION PREVENTION PLAN  
FOR STORM WATER GENERAL PERMIT  
U.S. ARMY CORPS OF ENGINEERS, MEMPHIS DISTRICT

**PART 1 LOCATION AND NATURE OF ACTIVITY**

The Contractor shall implement and diligently pursue all measures required by this Storm Water Pollution Prevention Plan (SWPPP). The purpose of the SWPPP is to control soil erosion and the resulting sediment to the extent necessary to prevent sediment from leaving the contract rights-of-way and prevent pollution of any water body caused by the runoff from the areas of construction activities under this contract. The Contractor shall review the SWPPP to determine requirements for compliance. In addition, the Contractor shall ascertain that his subcontractors have reviewed the plan, and that they comply with its provisions. The Contractor shall ensure that all subcontractors sign the CERTIFICATION located at the end of this section.

This project consists of construction of a new reinforced concrete bridge and demolition of an existing timber bridge, in Crittenden County, Arkansas. The project site is west of West Memphis, Arkansas. The old bridge is being replaced with a new bridge due to widening of the channel. A set of construction drawings showing the project location and the details of the new bridge construction will be located on the construction site at all times.

A set of construction drawings showing the project location and the details of installation of the environmental protection measures will be located on the construction site at all times. Flow arrows indicating drainage patterns are shown on the contract drawings.

No endangered species or their habitat will be adversely impacted by the project.

**PART 2 AREA AFFECTED**

The total area of the site, within the right-of-way limits, which will be impacted by construction, is approximately 22 acres, of which 14 acres may be disturbed during construction.

**PART 3 CONTROL OF POLLUTANTS DURING CONSTRUCTION**

Non-structural and/or structural measures shall be identified and constructed in a timely manner as to minimize the introduction of sediment into the 15 Mile Bayou as a result of storm water runoff. Controls shall be put in place prior to disturbance of soil and maintained until soils are stabilized.

### 3.1 NON-STRUCTURAL MEASURES

#### 3.1.1 General

Prior to the beginning of any construction, the Contracting Officer will identify all land resources to be preserved within the right-of-way. The Contractor shall provide effective protection for land, water and vegetation resources at all times. The Contractor shall construct or install temporary and/or permanent erosion and sedimentation control features as indicated herein to minimize pollutants entering 15 Mile Bayou, other water bodies, or wetlands. The Contractor shall not remove, cut, deface, injure, or destroy land resources including trees, shrubs, vines, grasses, topsoil, and land forms outside the construction right-of-way.

#### 3.1.2 Protection of Landscape

Trees, shrubs, vines, grasses, landforms and other landscape features indicated and defined on the contract drawings or as directed by the Contracting Officer to be preserved shall be clearly identified by marking, fencing, wrapping with boards, or other approved techniques.

#### 3.1.3 Reduction of Exposure of Unprotected Erodible Soils

All earthwork shall be planned and conducted to minimize the duration of exposure of unprotected soils. Vegetative ground cover shall not be destroyed, removed or disturbed more than 20 calendar days prior to grading or earth moving. Clearing shall progress in reasonably sized increments as needed to use the areas developed. To the extent feasible, material embankments, side slopes, back slopes, berms and any other exposed surfaces shall be stabilized by temporary seeding, mulching, fabric mats or other approved stabilization methods, as soon as possible after material placement, or within 14 days on areas that will remain unfinished more than 21 calendar days. Should construction be halted, for any reason, temporarily or permanently, for more than 21 days, in any portion of the site, temporary or permanent turfing measures, or other approved temporary stabilization of exposed areas, such as mulching, shall be accomplished within 14 days after construction is halted.

### 3.2 STRUCTURAL MEASURES

#### 3.2.1 General

Temporary erosion and sediment control measures such as silt fences, erosion control berms, check dams, and sedimentation basins shall be constructed and maintained until permanent drainage and erosion control facilities are complete and operative. Placement of perimeter controls shall commence with initiation of construction and shall remain in effect during the remainder of construction until final stabilization of those portions of the site upward of the perimeter control. Temporary erosion controls shall be maintained until final stabilization of exposed areas, after which they shall be removed. All structural devices shall be constructed in accordance with the standard drawing, TEMPORARY EROSION CONTROL DEVICES.

### 3.2.2 Silt Fences

Silt fences shall be constructed as a temporary structural measure to minimize erosion and sediment runoff. All necessary efforts shall be employed to minimize the entry of excavated material into 15 Mile Bayou, other water bodies, or wetlands. Close attention shall be paid to the repair of damaged silt fences resulting from end runs and undercutting. Should the fabric on a silt fence decompose or become ineffective, and the barrier is still necessary, the fabric shall be replaced promptly. Sediment deposits shall be removed when deposits reach one-third of the height of the barrier. Sediment removal shall include removal and disposition in a location where it will not erode into construction areas, watercourses or wetlands. When a silt fence is no longer required, it shall be removed. The immediate area occupied by the fence and any sediment deposits shall be shaped to an acceptable grade. The areas disturbed by this shaping shall be seeded in accordance with the paragraph "ESTABLISHMENT OF TURF" below.

### 3.2.3 Erosion Control Berms

Erosion control berms shall be constructed as a temporary structural measure to minimize erosion and sediment runoff. All necessary efforts shall be employed to minimize the entry of excavated material into 15 Mile Bayou, other water bodies, or wetlands. Soil shall be placed along top bank to effectively retain sediment immediately after completing each phase of work (e.g., clearing and grubbing, excavation, embankment, grading) in each independent runoff area. The erosion control berms shall be erected as work progresses. Erosion control berms shall be removed as needed for work to progress in the drainage area. Upon final removal of erosion control berms, they shall be shaped to an acceptable grade. The areas disturbed by this shaping shall be seeded in accordance with the paragraph "ESTABLISHMENT OF TURF" below. In the event that the erosion control berms begin to erode into the channel, the Contractor shall take action on the day that the erosion is noted, and protect the drainage area by installing straw bales at such locations as are necessary.

### 3.2.4 Check Dams

Check dams shall be constructed across inlet ditches, drains and swales using baled straw or equivalent devices to minimize sediment entry into 15 Mile Bayou, other water bodies, or wetlands. Check dams shall be inspected for sediment accumulation after each significant rainfall and sediment deposits shall be removed when deposits reach one-third of the height of the barrier. Sediment removal shall include removal and disposition in a location where it will not erode into construction areas, watercourses or wetlands. Close attention shall be paid to the repair of damaged bales or bags, end runs and undercutting. Necessary repairs to barriers or replacement shall be accomplished promptly. Barrier rows used to retain sediment shall be turned uphill at each end of each row. When a check dam is no longer required, it shall be removed. The immediate area occupied by the check dam and any sediment deposits shall be shaped to an acceptable grade. The areas disturbed by this shaping shall be seeded in accordance with the paragraph "ESTABLISHMENT OF TURF" below.

### 3.2.5 Sediment Basins

Sediment from construction areas with 10 or more disturbed acres at one time shall be trapped in temporary or permanent Sediment Basins. After each storm, the basins shall be allowed to settle for 24 to 48-hours after which the basins shall be pumped dry. In order to maintain basin effectiveness, accumulated sediment shall be removed when the depth of sediment reaches one-third of the depth of structure in any part of the pool. Overflow shall be controlled by paved weir, by vertical overflow pipe draining from the surface, or by a spillway protected by baled straw filter barriers in the spillway and at the outlet toe of the spillway. The collected topsoil sediment shall be reused for fill on the construction site, and/or conserved for use at another site(s). If used, the basins shall provide at least 3,600 cubic feet of storage for each acre drained. Where such basins are not used, other equivalent sediment control measures are required.

### 3.2.6 Other Measures

Other temporary erosion and sediment control measures such as dikes, swales, and drains may be used with, or in lieu of, the above-mentioned measures provided they are consistent with Best Management Practices (BMPs). They shall be maintained until permanent drainage and erosion control facilities are complete and operative. Earthen erosion control features shall be compacted and stabilized immediately with vegetation as specified in the following paragraphs entitled "Seeding" and "Mulching."

### 3.2.7 Velocity Dissipation Devices

Should drains or swales be used, they shall be constructed with velocity dissipation devices (check dams) to reduce the need for more stringent erosion control practices in the swale or drain. These devices shall be removed after the erosive areas have been stabilized.

### 3.2.8 Off-site Tracking of Sediment

Off-site tracking of sediment will be minimized by having most of the construction equipment delivered to and removed from the worksite by trailer. Locations where vehicles enter or exit the worksite shall be inspected to minimize off-site tracking of sediment.

## PART 4 CONTROL OF POLLUTANTS AFTER CONSTRUCTION

### 4.1 ESTABLISHMENT OF TURF

#### 4.1.1 General

Turf shall be established as a permanent erosion control measure along any areas which are disturbed during construction. All material embankments, all berm areas, and any other disturbed areas shall be turfed. Turf shall be established in accordance with the Contract Specifications.

#### 4.1.2 Fertilizer

Fertilizer shall be distributed uniformly over the areas to be seeded at a rate which will supply not less than 40 pounds of available nitrogen, 40 pounds of available phosphorous, and 40 pounds of potash per acre.

#### 4.1.3 Seeding

Seed sown for permanent turfing shall be sown as specified in the technical specifications. Temporary seeding shall consist of grasses appropriate for the season when they are sown. A satisfactory method of sowing shall be employed, using approved mechanical power-drawn seeders, mechanical hand-seeders, broadcast-seeders, or other approved methods. When conditions are such by reason of drought, high winds, excessive moisture, or other factors that satisfactory results are not likely to be obtained, work shall be halted as directed by the Contracting Officer. Such work may resume only when conditions are favorable or when approved alternative or corrective measures and procedures have been identified and approved by the Contracting Officer. If inspection either during seeding operations or after there is a show of green indicates that areas have been left unplanted, additional seed shall be sown.

#### 4.1.4 Mulching

If used, mulch shall be materials that do not contain noxious grass or weed seed that might be detrimental to the turf being established or to adjacent farmland. Mulch shall be spread uniformly in a continuous blanket, using two tons-per-acre of straw mulch or 1,200 pounds-per-acre of wood cellulose fiber mulch.

### 4.2 STATE AND LOCAL CONTROLS

There are no known State or local erosion and sediment control requirements applicable to this work other than those met by the requirements of this permit. In the event that there are State or local erosion and sediment control requirements, it shall be the responsibility of the Contractor to identify and comply with all applicable requirements. Chemical waste units shall be used at the site, with disposal in accordance with State and local regulations. Measures shall be in place to ensure compliance with State and local waste disposal, sanitary sewer, or septic system regulations. Water Quality Standards of receiving streams shall be maintained during and after construction in accordance with requirements of the State Water Quality Certification.

### PART 5 RUNOFF COEFFICIENT, IMPERVIOUS AREAS, SOILS

The runoff coefficient prior to construction is estimated to range between 0.10 and 0.30. Once the material embankment and other disturbed areas have been re-vegetated, the runoff coefficient should remain in approximately the same range with no increase in impervious areas. Soils in the area are a silty clay material. For further information regarding soil borings contact the Memphis District Office of the U.S. Army Corps of Engineers.

### PART 6 RECEIVING WATER

The receiving water is the 15 Mile Bayou. The only existing surface waters within construction right-of-way limits are waters in agricultural ditches, roadway ditches, and 15 Mile Bayou. Locations of storm water discharges will be more specifically identified by the Contractor in his Environmental Protection Plan submitted to the Government for approval 15 days after his receipt of Notice to Proceed. There are no Total Maximum Daily Loads (TDMLs) applicable for the immediate receiving waters and since control measures will be in place to minimize sediment discharge, the impact upon the ultimate receiving stream will be negligible. No non-storm water discharges are anticipated to be combined with storm water runoff.

## PART 7 INSPECTIONS

### 7.1 GENERAL

Quality Control Representatives shall inspect disturbed areas of the construction site, areas used for storage of materials that are exposed to precipitation that have not been finally stabilized, structural control measures, and locations where vehicles enter or exit the site every seven calendar days and within 24-hours of the end of a storm that is 0.5-inches or greater. Where sites have been stabilized, inspections shall be conducted at least once every month.

### 7.2 DISTURBED AREAS AND AREAS USED FOR MATERIAL STORAGE

Disturbed areas and areas used for material storage that are exposed to precipitation shall be inspected for evidence of, or the potential for, pollutants entering the drainage system. Erosion and sediment control measures identified in the plan shall be observed to ensure correct operation. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impact to receiving waters. Locations where vehicles enter or exit the site shall be inspected for evidence of off-site sediment tracking.

### 7.3 MODIFICATION OF POLLUTION PLAN

Based on the results of the inspection referenced in the paragraph entitled "DISTURBED AREAS AND AREAS USED FOR MATERIAL STORAGE," the site description identified in Part 1 and Part 2 of this plan shall be revised as appropriate, but in no case more than seven calendar days following the inspection. Such modification shall provide for timely implementation of any changes to the plan within seven calendar days following the inspection.

### 7.4 REPORTS

A report summarizing the scope of the inspection, name(s) and qualifications of personnel making the inspection, the date(s) of the inspection, major observations relating to the implementation of the SWPPP, and actions taken shall be recorded and retained by the Contracting Officer as part of the SWPPP for at least three years from the date the site is finally stabilized.

## PART 8 OTHER CONSIDERATIONS

8.1 LOCATION OF CONSTRUCTION IN REGARD TO WATERS CLASSIFIED IN 10 CSR  
20-7.013

Construction is not within 1,000 feet of waters classified in 10 CSR  
20-7.013, Water Quality Standards, as:

- a. Public drinking water supply lakes
- b. Outstanding National Resource Waters
- c. Outstanding State Resource Waters
- d. Streams designated for cold water sport fishery
- e. A lake in EPA's Clean Lakes Program

8.2 PROXIMITY OF SITE TO MAJOR RESERVOIRS

Construction is not within 100 feet of waters classified as major  
reservoirs.

PART 9 DEFINITIONS

9.1 BEST MANAGEMENT PRACTICES (BMPS)

Schedules of activities, prohibitions of practices, maintenance  
procedures, and other management practices to prevent or reduce the  
pollution of waters of the State. BMPs also include treatment  
requirements, operation procedures and practices to control plant site  
runoff, spillage or leaks, sludge or waste disposal, or drainage from  
raw material storage.

9.2 COMMENCEMENT OF CONSTRUCTION

The initial disturbance of soils associated with clearing and  
grubbing, or other construction activities.

9.3 DRAINAGE SWALE

A drainage way with a lining of grass, riprap, asphalt, concrete, or  
other material installed to convey runoff without causing erosion.

9.4 CHECK DAM

Small temporary dams constructed across a swale or drainage ditch to  
reduce the velocity of runoff flows.

9.5 FINAL STABILIZATION

All soil-disturbing activities at the site have been completed, and a  
uniform perennial vegetative cover with a density of 85 percent of the  
cover for the area has been established or equivalent stabilization  
measures (such as the use of mulches or geo-textiles) have been  
employed.

PART 10 CERTIFICATION

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

Dennis J. Kamper, P.E., Chief, Eng. and Const. Division, COE (901)  
544-3227

\_\_\_\_\_  
Name & Official Title Phone No.

\_\_\_\_\_  
Signature Date Signed

I certify under penalty of law that I understand the terms and conditions of the general National Pollutant Discharge Elimination System (NPDES) permit that authorizes the storm water discharges associated with industrial activity from the construction site identified as part of this certification.

\_\_\_\_\_  
Name & Official Title of Contractor Phone No.

\_\_\_\_\_  
Signature Date Signed

\_\_\_\_\_  
Name & Official Title of Sub Contractor Phone No.

\_\_\_\_\_  
Signature Date Signed

*For multiple Sub Contractors, attach additional Certification Sheets as necessary.*

-- End of Section --