

DACW66-05-B-0016 County Bridge Replacement 10 & 15 Mile Bayou Item 2, Mile 18.8 Crittenden County, AR			
Quantities Last Updated: (Amendments - 1)		7/18/05 7:42 AM	
Item	Quantity Calculations Description For Lump Sum Items	Estimated Quantity	U/M
1	Mobilization & Demobilization	1	LS
2	Clearing & Grubbing	1	LS
2a	Total ROW	22	AC
3	Excavation	34,000	CY
4	Roadway and Field Access Ramp	1	LS
4a	Embankment	2,060	CY
5	Aggregate Surfacing	490	TN
6	Finish Dressing, Fertilizing, Seeding, and Mulching	1	LS
6a	Total ROW	22	AC
7	Bedding Material	600	TN
8	Riprap	1,200	TN
9	Steel H-Piles	2,640	LF
10	Cast-In-Place Structural Concrete	1	LS
10a	Concrete	48	CY
10b	Reinforcing	5,100	LB
11	Corrugated Metal Pipe, 36-inch	40	LF
12	Guardrail	1	LS
12a	Guardrail	550	LF
13	Environmental Protection	1	LS
13a	Total ROW	22	AC
14	Bridge at Mile 18.8	1	LS
15	Bridge Demolition	1	LS
<p>It is to be expressly understood that the accuracy of these estimates is in no way warranted and that the furnishing of this information to a bidder will not relieve him of his responsibility to estimate the quantities involved. It is further to be expressly understood that in no case will such estimate be used as a basis of claim against the Government.</p> <p>If you have any questions about these quantities, please contact Neal E. Newman at neal.e.newman@mvm02.usace.army.mil, 901-544-0890 (Work), or 901-544-4924 (Fax).</p>			