

Project: TROTTERS, MS; LANDSIDE BERM, PARCEL 1; MRL - CONSTRUCTION
 Location: Tunica County, MS
 W912EQ-05-B-0019

BI #	BID ITEM	Qty	UM
1	Mobilization & Demobilization	1	LS
2	Clearing and Grubbing	1	LS
	Berm	79	AC
	Fill Area 1	32.6	AC
	Fill Area 2	10.7	AC
	Fill Area 3	5.2	AC
	Fill Area 4	30.4	AC
	Pit	39	AC
	Borrow Area 1	16.0	AC
	Borrow Area 2	8.0	AC
	Borrow Area 3	14.9	AC
3	Turf (borrow area)	1	LS
	Dress., Fertilize and Seed see item 2 for breakout	39	AC
4	G. Growth Turf (fill area)	1	LS
	Bermuda sod or sprig see item 2 for breakout	79	AC
5	Ditch Excavation	1	LS
		300	CY
6	Environmental Protection	1	LS
	LF of berm	10,500	LF
7	Fill Material Placement	340,000	CY
	Fill Area 1	144,100	CY
	Fill Area 2	37,000	CY
	Fill Area 3	30,200	CY
	Fill Area 4	128,700	CY
	Pit, max. available:	128,700	CY
	Borrow Area 1	207,100	CY
	Borrow Area 2	103,640	CY
	Borrow Area 3	192,630	CY

Total average weighted haul = 1.1 miles.

Acreage for item 4 depends on how much area is denuded.

It is to be expressly understood that the accuracy of these estimates is in no way warranted and that the furnishing of this information to a bidder will not relieve him of his responsibility to estimate the quantities involved. It is further to be expressly understood that in no case will such estimate be used as a basis of claim against the Government.

If you find errors in these, we would appreciate your comments.

You may contact Richard Hurst or Jerry Welch for questions on these quantities.

You may email Richard at

Richard.H.Hurst@MVM02.USACE.ARMY.MIL

If you do not have email, you may contact him at 901.544.0886.

Jerry's contact information is listed on the web page for this solicitation.

Quantities as of 8/11/05.

Quantities reflect no Ammendments.