

CAIRO-MOUND CITY, IL PARCEL 4				W912EQ-07-B-0001	
SEEPAGE CONTROL PROJECT					
ALEXANDER CO., IL; MRL - CONSTRUCTION					
Point of Contact:		Quantities reflect: AMENDMENTS: None			
Richard Hurst 901-544-0886		as of		23-Apr-07	
Fax 901.544.4924					
Richard.Hurst@us.army.mil					
No.	Bid Item	Quantity	Unit	Sub Totals	Totals
1	Mobilization and Demobilization	1	LS		
2	Clearing and Grubbing	1	LS		
	Clearing work area	21	ACR		
3	Mowing of the Grass	1	LS		
	Mowing Grass	57	ACR		
4	Piezometer Installation	3	EA		
5	Excavation and Backfill	30,500	CY		
6	Aggregate Resurfacing	1	LS		
	Spread/Compact Gravel	1,400	CCY		
	Prepare subgrade	6,770	LF		
7	Soil-Bentonite Slurry Trench Cut Off Wall (for depths to 60-feet)	376,020	SF		
	Bentonite	1,910	TON		
8	Soil-Bentonite Slurry Trench Cut Off Wall (for depths greater than 60-feet)	188,010	SF		
	Bentonite	955	TON		
9	Guaranteed Growth Turf	1	LS		
	Establish Turf	21	ACR		
10	Environmental Protection	1	LS		
	Total length:	6,567	LF		
<p style="color: red;">It is to be expressly understood that the accuracy of these estimates is in no way warranted and that the furnishing of this information to a bidder will not relieve him of his responsibility to estimate the quantities involved. It is further to be expressly understood that in no case will such estimate be used as a basis of claim against the Government.</p>					
If you find errors in these, we would appreciate your comments.					