

DACW66-01-B-0020 Caruthersville, MO Relief Wells, Pemiscot County, MO			
Quantities Last Updated: (Thru Amendent 1)			9/5/01 12:21 PM
Item	Quantity Calculations Description For Lump Sum Items	Estimated Quantity	U/M
1	Mobilization & Demobilization	1	LS
2	Clearing	1	LS
2.a	Clearing	16	AC
2.b	Total Area In ROW	39	AC
10	Reinforced Concrete Culvert Pipe 18", 24", 36", 42" and 48";Concrete Junction Manholes, Concrete Manholes over Relief Wells, and Connecting Pipes, and Concrete Junction Box	1	LS
10.a	18" RCP	915	LF
10.b	24" RCP	995	LF
10.c	36" RCP	441	LF
10.d	42" RCP	900	LF
10.e	48" Rcp	550	LF
10.f	40" x 65" Arch Pipe	8	LF
10.g	Precast Manholes	23	EA
10.h	Excavation	16,736	CY
10.i	Junction Box	1	EA
10.ia	Junction Box Concrete	34	CY
10.ib	Junction Box Reinforcing	1.9	TN
10.j	Granular Backfill	1,540	TN
10.ik	Compacted Random	1,784	CY
11	Fertilizing and Seeding	1	LS
11.a	Fertilizing and Seeding	16	AC
12	Environmental Protection	1	LS
12.a	Erosion Control	1,500	LF
<p>It is to be expressly understood that the accuracy of these estimates is in no way warranted and that the furnishing of this information to a bidder will not relieve him of his responsibility to estimate the quantities involved. It is further to be expressly understood that in no case will such estimate be used as a basis of claim against the Government.</p>			