TBM STA. 226+00±
CHISELED SQUARE IN HEADWALL
ELEV.: 297.95'
N: 1971545.7016
E: 2435652.8851

STEPHEN D. WILLIAMS

MH 28–STA 220+44±
Δ=79°42'14"RT

495± TONS OF GROUTED RIP-RAP (1 LAYER)

THIS CONTRACT ← → BY OTHERS

COLLEGE ROAD

44± LF OF 48" SANITARY SEWER

856± LF OF 48" SANITARY SEWER

50' PERMANENT EASEMENT

60' TEMPORARY CONSTRUCTION EASEMENT

MATCHLINE STA. 220+00 SHEET C1.15

END UPPER CAMP CREEK INTERCEPTOR SOUTH

STEPHEN D. WILLIAMS

MATCHLINE STA. 220+00 SHEET C1.01
UPPER CAMP CREEK NORTH INTERCEPTOR

PLAN
1"=100'
50 0 50 100 150

CONTRACTOR NOTE: ALL EXISTING UTILITIES ON THESE PLANS ARE FOR INFORMATION ONLY. NO GUARANTEE IS OFFERED OR TO BE IMPLIED REGARDING THE ACCURACY OF THE LOCATIONS OF EXISTING UTILITIES INDICATED ON THESE PLANS. THE CONTRACTOR IS RESPONSIBLE FOR ACCURATELY DETERMINING THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION.

NEW 108" DIA. MH
STA. 220+44
RIM ELEVATION
@ 300.0 ±

EXISTING 72" DIA. MH
STA. 229+70
RIM ELEVATION
@ 299.8 ±

THIS CONTRACT ← → BY OTHERS

APPROXIMATE 100 YEAR FLOOD

APPROXIMATE EXISTING GRADE

MATCHLINE STA. 235+00

44± LF OF 48" SANITARY SEWER AT 0.00072 FT/FT SLOPE

856± LF OF 48" SANITARY SEWER AT 0.00473 FT/FT SLOPE

INV OUT 266.73
INV IN 266.83

STA. 220+70±

CREEK CROSSING
120± LF OF 42" SANITARY SEWER INSIDE CONCRETE ENCASEMENT

STA. 221+90±

INV OUT 270.84
INV IN 270.94

PROFILE
HORZ: 1"=50'
VERT: 1"=10'

NO.	DATE	REVISIONS	BY	APP'D

DESIGNED TMH	DATE OCTOBER 2003
DRAWN TMH	SCALE AS NOTED
CHECKED CRF	JOB NO. 16535.05

EAIWEI, LLC
WAGGONER
660 BRIARWOOD DRIVE SUITE 515
JACKSON, MS 39206

100% SET

DESOTO COUNTY REGIONAL UTILITY AUTHORITY
UPPER CAMP CREEK INTERCEPTOR SOUTH
DESOTO COUNTY, MISSISSIPPI

DESOTO COUNTY REGIONAL UTILITY AUTHORITY

PLAN AND PROFILE SHEET
STA. 220+00 to EOP

PROJECT NO.	
16535.05	
CONTRACT	SHEET
1	C1.16